

(1) SAWCUT, REMOVE, AND DISPOSE OF EXISTING BITUMINOUS PAVEMENT. (2) SAWCUT, REMOVE AND DISPOSE OF EXISTING CONCRETE PAVEMENT. 3 SAWCUT, REMOVE, AND DISPOSE OF EXISTING CONCRETE CURB AND

(4) REMOVE AND DISPOSE OF EXISTING GRAVEL.

(5) REMOVE AND DISPOSE OF EXISTING AG-LIME.

6 REMOVE AND DISPOSE OF EXISTING TREES, DOWNED TREES, STUMPS, AND BRUSH.

7 REMOVAL OF EXISTING BUS GARAGE BY OTHERS. REMOVE AND DISPOSE OF EXISTING CONCRETE APRON AND FOOTINGS. COORDINATE WITH POWER COMPANY TO DISCONNECT POWER.

8 FIBER OPTIC CABLE RELOCATION BY OTHERS. COORD. WITH UTILITY

(9) REMOVE AND DISPOSE OF EXISTING FENCING AND ALL RELATED FOOTINGS.

(10) SALVAGE AND RELOCATE EXISTING GOAL POST.

(1) REMOVE AND DISPOSE OF EXISTING TIMBERS SURROUNDING SHOT PUT THROWING SECTOR.

(12) SALVAGE EXISTING DISCUS CAGE. REMOVE AND DISPOSE OF ANY CONCRETE FOOTINGS

(13) PROTECT FLARED END SECTION.

(16) REMOVE AND DISPOSE OF EXISTING STORMWATER STRUCTURE.

(17) REMOVE AND DISPOSE OF EXISTING PIPE.

(18) REMOVE AND DISPOSE OF EXISTING FLARED END SECTION.

(19) REMOVE AND DISPOSE OF EXISTING LANDSCAPING.

(20) PROTECT EXISTING HYDRANT.

21) REMOVE AND DISPOSE OF EXISTING POSTS AND ANY RELATED FOOTINGS

(22) REMOVE AND DISPOSE OF EXISTING BACKSTOP FENCING AND ANY RELATED FOOTINGS.

(23) REMOVE AND SALVAGE EXISTING BALL FIELD BASES, AS NEEDED FOR UTILITY INSTALLATION. DOCUMENT EXACT LOCATION OF THE BASE FOR USE DURING THE REINSTALLATION.

UE V

SYMBOL LEGEND







www.larsonengr.com

C 2024 Larson Engineering, Inc. All rights reserved.

CONSTRUCTION DOCUMENTS

| NUMBER | DESCRIPTION | DATE |
|--------|--------------|----------|
| 1 | ADDENDUM #1 | 02/12/24 |
| 2 | ADDENDUM #2 | 02/15/24 |
| 3 | ADDENDUM #3 | 02/22/24 |
| 4 | STATE REVIEW | 05/31/24 |
| 5 | PR 03 | 08/01/24 |
| 6 | PR 04 | 08/16/24 |

I hereby certify that this plan, specifications or report was prepared by me or under my direct supervision and that I am a duly licensed Professional Engineer under the laws of the state of Minnesota

Justin Nielsen, P.E. Jato Ninh /01/2024 Registration No. 52687





DEMOLITION PLAN





KEY PLAN







www.larsonengr.com

(C) 2024 Larson Engineering, Inc. All rights reserved.

CONSTRUCTION DOCUMENTS

| NUMBER | DESCRIPTION | DATE |
|--------|--------------|----------|
| 1 | ADDENDUM #1 | 02/12/24 |
| 2 | ADDENDUM #2 | 02/15/24 |
| 3 | ADDENDUM #3 | 02/22/24 |
| 4 | STATE REVIEW | 05/31/24 |
| 5 | PR 03 | 08/01/24 |
| 6 | PR 04 | 08/16/24 |

I hereby certify that this plan, specifications or report was prepared by me or under my direct supervision and that I am a duly licensed Professional Engineer under the laws of the state of Minnesota.

Print Name: Justin Nielsen, P.E. Signature: Justin Take Date: 02/01/2024 Registration No. 52687





DEMOLITION PLAN





| •••••• | |
|-----------|---|
| | REMOVE AND DISPOSE OF EXISTING BITUMINOUS PAVEMENT SECTION |
| 4 4 4 4 4 | REMOVE AND DISPOSE OF EXISTING CONCRETE PAVEMENT SECTION |
| | REMOVE AND DISPOSE OF EXISTING GRAVEL SECTION |
| | REMOVE AND DISPOSE OF |

KEY NOTES

- 1 SAWCUT, REMOVE, AND DISPOSE OF EXISTING BITUMINOUS PAVEMENT.
- 2 SAWCUT, REMOVE AND DISPOSE OF EXISTING CONCRETE PAVEMENT.
- 3 SAWCUT, REMOVE, AND DISPOSE OF EXISTING CONCRETE CURB AND GUTTER.
- (4) REMOVE AND DISPOSE OF EXISTING GRAVEL.
- 5 REMOVE AND DISPOSE OF EXISTING AG-LIME.
- 6 REMOVE AND DISPOSE OF EXISTING TREES, DOWNED TREES, STUMPS, AND BRUSH.
- 7 REMOVAL OF EXISTING BUS GARAGE BY OTHERS. REMOVE AND DISPOSE OF EXISTING CONCRETE APRON AND FOOTINGS. COORDINATE WITH POWER COMPANY TO DISCONNECT POWER.
- 8 FIBER OPTIC CABLE RELOCATION BY OTHERS. COORD. WITH UTILITY COMPANY
- (9) REMOVE AND DISPOSE OF EXISTING FENCING AND ALL RELATED FOOTINGS.
- (10) SALVAGE AND RELOCATE EXISTING GOAL POST.
- (1) REMOVE AND DISPOSE OF EXISTING TIMBERS SURROUNDING SHOT PUT THROWING SECTOR.
- (12) SALVAGE EXISTING DISCUS CAGE. REMOVE AND DISPOSE OF ANY CONCRETE FOOTINGS
- (13) PROTECT FLARED END SECTION.
- (14) PROTECT EXISTING ELECTRICAL.
- (15) PROTECT EXISTING GAS LINE.
- (16) REMOVE AND DISPOSE OF EXISTING STORMWATER STRUCTURE.
- (17) REMOVE AND DISPOSE OF EXISTING PIPE.
- (18) REMOVE AND DISPOSE OF EXISTING FLARED END SECTION.
- (19) REMOVE AND DISPOSE OF EXISTING LANDSCAPING.
- (20) PROTECT EXISTING HYDRANT.
- 21) REMOVE AND DISPOSE OF EXISTING POSTS AND ANY RELATED
- FOOTINGS
 REMOVE AND DISPOSE OF EXISTING BACKSTOP FENCING AND ANY RELATED FOOTINGS.
- 23 REMOVE AND SALVAGE EXISTING BALL FIELD BASES, AS NEEDED FOR UTILITY INSTALLATION. DOCUMENT EXACT LOCATION OF THE BASE FOR USE DURING THE REINSTALLATION.

DEMOLITION NOTES

1. See Sheet C100 for Demolition Notes.





www.larsonengr.com

(C) 2024 Larson Engineering, Inc. All rights reserved.

| CONSTRUCTION |
|--------------------------|
| DOCUMENTS |
| REVISION SCHEDULE |

| NUMBER | DESCRIPTION | DATE |
|--------|--------------|----------|
| 1 | ADDENDUM #1 | 02/12/24 |
| 2 | ADDENDUM #2 | 02/15/24 |
| 3 | ADDENDUM #3 | 02/22/24 |
| 4 | STATE REVIEW | 05/31/24 |
| 5 | PR 03 | 08/01/24 |
| 6 | PR 04 | 08/16/24 |

I hereby certify that this plan, specifications or report was prepared by me or under my direct supervision and that I am a duly licensed Professional Engineer under the laws of the state of Minnesota.

Print Name: Justin Nielsen, P.E. Signature: Justin Markov Date: 02/01/2024 Registration No. <u>52687</u>





DEMOLITION PLAN





KEY PLAN









GENERAL

| | PROPERTY LINE |
|---------|--------------------------|
| · · · · | EASEMENT LINE |
| · · | RIGHT-OF-WAY LINE |

KEY NOTES





- $\langle 30 \rangle$ RESTORE EXISTING STRIPING
- $\langle 31 \rangle$ SAND VOLLEYBALL COURT, SEE DETAIL 11/C502
- $\langle 32 \rangle$ FURNISH AND INSTALL VOLLEYBALL STANDARDS AND NET, SEE SPECIFICATIONS
- $\langle 33 \rangle$ REINSTALL SALVAGED BALL FIELD BASES





www.larsonengr.com

 \bigcirc 2024 Larson Engineering, Inc. All rights reserved.

| CONSTRUCTION |
|--------------------------|
| DOCUMENTS |
| REVISION SCHEDULE |

| NUMBER | DESCRIPTION | DATE |
|--------|--------------|----------|
| 1 | ADDENDUM #1 | 02/12/24 |
| 2 | ADDENDUM #2 | 02/15/24 |
| 3 | ADDENDUM #3 | 02/22/24 |
| 4 | STATE REVIEW | 05/31/24 |
| 5 | PR 03 | 08/01/24 |
| 6 | PR 04 | 08/16/24 |

I hereby certify that this plan, specifications or report was prepared by me or under my direct supervision and that I am a duly licensed Professional Engineer under the laws of the state of Minnesota.

Print Name: Justin Nielsen, P.E. Signature: July Mahn Date: 02/01/2024 Registration No. 52687





PAVING & DIMENSION PLAN





| GENERAL | |
|-------------|-------------------|
| | |
| | |
| · · · · · · | EASEMENT LINE |
| · · | RIGHT-OF-WAY LINE |

KEY NOTES

| 1 LIGHT DUTY BITUMINOUS PAVEMENT, SEE DETAIL 1/C500 |
|--|
| $\langle 2 \rangle$ HEAVY-DUTY BITUMINOUS PAVEMENT, SEE DETAIL 2/C500 |
| (3) MATCH EXISTING BITUMINOUS PAVEMENT SECTION, ASSUME HEAVY-DUTY SECTION FOR BIDDING PURPOSE |
| 4 LIGHT-DUTY CONCRETE PAVEMENT, SEE DETAIL 3/C500 |
| 5 HEAVY-DUTY CONCRETE PAVEMENT, SEE DETAIL 4/C500 |
| 6 B612 CONCRETE CURB AND GUTTER, SEE DETAIL 5/C500 |
| $\langle 7 \rangle$ SURMOUNTABLE CURB AND GUTTER, SEE DETAIL 6/C500 |
| 8 B618 CONCRETE CURB AND GUTTER, SEE DETAIL 7/C500 |
| 9 BOLLARD, SEE DETAIL 8/C500 |
| 10 PARKING SIGN AND POST, SEE DETAIL 9/C500 _A: ADA PARKING STALL _B: STOP _C: DO NOT ENTER _D: DROP OFF LANE KEEP RIGHT _E: BUSES AND DELIVERY ONLY _F: ADA LOADING ZONE |
| ACCESSIBLE RAMP, SEE DETAIL 10/C500 _A: TYPE 1 _B: TYPE 2 |
| 12 FLAGPOLE, SEE DETAIL 11/C500 |
| (13) BASKETBALL GOAL, SEE DETAIL 13/C500 |
| (14) BASKETBALL COURT STRIPING, SEE DETAIL 12/C500 |
| (15) PARKING SIGN, POST, AND BOLLARD, SEE DETAIL 14/C500 _A: ADA PARKING STALL _B: NO PARKING ACCESS AISLE |
| (16) DISCUS EVENT, DEE DETAIL 1/C501 |
| (17) SHOT PUT EVENT, SEE DETAIL 2/C501 |
| (18) 4' FENCING, SEE DETAIL 3/C501 |
| (19) MONUMENT SIGN, SEE ARCH./STRL. |
| $\langle 20 \rangle$ BIKE RACK, SEE SPECIFICATIONS |
| $\langle 21 \rangle$ BENCH, SEE SPECIFICATIONS |
| $\langle 22 \rangle$ GAS METER, SEE MECH. |
| $\langle 23 \rangle$ LIGHT POLE, SEE ELEC. |
| $\langle 24 \rangle$ INSTALL SALVAGED GOAL POST, SEE DETAIL 3/C503 |
| $\langle 25 \rangle$ TRANSITION CURB |
| 26 BALL FIELD BACKSTOP, SEE DETAIL 1/C503 |
| 27 AG-LIME SURFACING, SEE DETAIL 2/C503 |
| $\langle 28 \rangle$ DISCUS EVENT WITH SALVAGED CAGE, SEE DETAIL 1/C501 |
| 29 FOUR SQUARE STRIPING 16'X16' |
| $\langle 30 \rangle$ RESTORE EXISTING STRIPING |
| $\langle 31 \rangle$ SAND VOLLEYBALL COURT, SEE DETAIL 11/C502 |
| $\begin{array}{ c c c c c }\hline\hline & & \hline & & & \hline & & & \hline & & & \hline & & & & & \hline & & & & & \hline & & & & & \hline & & & & & & \hline & & & & & \hline & & & & & & & \hline & & & & \hline & \\ & & & &$ |
| 33 REINSTALL SALVAGED BALL FIELD BASES |
| |

www.larsonengr.com

© 2024 Larson Engineering, Inc. All rights reserved.

| CONSTRUCTION DOCUMENTS | |
|---------------------------|--|
| | |

| NUMBER | DESCRIPTION | DATE |
|--------|--------------|----------|
| 1 | ADDENDUM #1 | 02/12/24 |
| 2 | ADDENDUM #2 | 02/15/24 |
| 3 | ADDENDUM #3 | 02/22/24 |
| 4 | STATE REVIEW | 05/31/24 |
| 5 | PR 03 | 08/01/24 |
| 6 | PR 04 | 08/16/24 |

I hereby certify that this plan, specifications or report was prepared by me or under my direct supervision and that I am a duly licensed Professional Engineer under the laws of the state of Minnesota.

Print Name: Justin Nielsen, P.E. Signature: Justin Michaelsen, P.E. Date: 02/01/2024 Registration No. 52687

PAVING & DIMENSION PLAN

- A: TYPE 1
- (12) FLAGPOLE, SEE DETAIL 11/C500
- (13) BASKETBALL GOAL, SEE DETAIL 13/C500
- $\langle 14 \rangle$ BASKETBALL COURT STRIPING, SEE DETAIL 12/C500
- (15) PARKING SIGN, POST, AND BOLLARD, SEE DETAIL 14/C500 _A: ADA PARKING STALL _B: NO PARKING ACCESS AISLE
- $\langle 16 \rangle$ DISCUS EVENT, DEE DETAIL 1/C501
- $\langle 17 \rangle$ SHOT PUT EVENT, SEE DETAIL 2/C501
- $\langle 18 \rangle$ 4' FENCING, SEE DETAIL 3/C501
- $\langle 19 \rangle$ MONUMENT SIGN, SEE ARCH./STRL.
- $\langle 20 \rangle$ BIKE RACK, SEE SPECIFICATIONS
- $\langle 21 \rangle$ BENCH, SEE SPECIFICATIONS
- $\langle 22 \rangle$ GAS METER, SEE MECH.
- $\langle 23 \rangle$ LIGHT POLE, SEE ELEC.
- (24) INSTALL SALVAGED GOAL POST, SEE DETAIL 3/C503
- $\langle 25 \rangle$ TRANSITION CURB
- 26 BALL FIELD BACKSTOP, SEE DETAIL 1/C503
- (27) AG-LIME SURFACING, SEE DETAIL 2/C503
- $\langle 28 \rangle$ DISCUS EVENT WITH SALVAGED CAGE, SEE DETAIL 1/C501
- $\langle 29 \rangle$ FOUR SQUARE STRIPING 16'X16'
- $\langle 30 \rangle$ RESTORE EXISTING STRIPING
- $\langle 31 \rangle$ SAND VOLLEYBALL COURT, SEE DETAIL 11/C502
- $\langle 32 \rangle$ FURNISH AND INSTALL VOLLEYBALL STANDARDS AND NET, SEE SPECIFICATIONS
- $\langle 33 \rangle$ REINSTALL SALVAGED BALL FIELD BASES

 $\langle 14 \rangle$

 $\langle 4 \rangle$

(31)

www.larsonengr.com

© 2024 Larson Engineering, Inc. All rights reserved.

| CONSTRUCTION |
|--------------------------|
| DOCUMENTS |
| REVISION SCHEDULE |

| NUMBER | DESCRIPTION | DATE |
|--------|--------------|----------|
| 1 | ADDENDUM #1 | 02/12/24 |
| 2 | ADDENDUM #2 | 02/15/24 |
| 3 | ADDENDUM #3 | 02/22/24 |
| 4 | STATE REVIEW | 05/31/24 |
| 5 | PR 03 | 08/01/24 |
| 6 | PR 04 | 08/16/24 |

I hereby certify that this plan, specifications or report was prepared by me or under my direct supervision and that I am a duly licensed Professional Engineer under the laws of the state of Minnesota.

Print Name: Justin Nielsen, P.E. Signature: Juto Micha Date: 02/01/2024 Registration No. 52687

PAVING & DIMENSION PLAN

950 PROPOSED CONTOURS - MAJOR INTERVAL PROPOSED CONTOURS - MINOR INTERVAL GRADE SLOPE

_____ SEDIMENT LOG, SEE DETAIL 7/C501

RIP-RAP, SEE DETAIL 4/C501 AND 5/C501

INLET PROTECTION, SEE DETAIL 9/C501

ROCK CONST. ENTRANCE, SEE DETAIL 6/C501 (EXACT LOCATION TO BE DETERMINED)

GO - GUTTER OUT **B - BITUMINOUS**

C - CONCRETE EOF - EMERGENCY OVERFLOW

G - GROUND FFE - FINISH FLOOR ELEVATION

SPOT ABBREVIATIONS:

(*) - EXISTING TO BE VERIFIED

© 2024 Larson Engineering, Inc. All rights reserved.

| CONSTRUCTION |
|-------------------------|
| DOCUMENTS |
| EVISION SCHEDULE |

| NUMBER | DESCRIPTION | DATE |
|--------|--------------|----------|
| 1 | ADDENDUM #1 | 02/12/24 |
| 2 | ADDENDUM #2 | 02/15/24 |
| 3 | ADDENDUM #3 | 02/22/24 |
| 4 | STATE REVIEW | 05/31/24 |
| 5 | PR 03 | 08/01/24 |
| 6 | PR 04 | 08/16/24 |

I hereby certify that this plan, specifications or report was prepared by me or under my direct supervision and that I am a duly licensed Professional Engineer under the laws of the state of Minnesota.

Print Name: Justin Nielsen, P.E. Junto Nicho Date: 02/01/2024 Registration No. 52687

GRADING & EROSION CONTROL PLAN

C300

KEY PLAN

GRADING NOTES

1. See Sheet C300 for Grading Notes.

EROSION CONTROL NOTES

1. See Sheet C700 for Erosion Control Notes.

SYMBOL LEGEND

PROPOSED CONTOURS - MINOR INTERVAL GRADE SLOPE

_____ SEDIMENT LOG, SEE DETAIL 7/C501

RIP-RAP, SEE DETAIL 4/C501 AND 5/C501

INLET PROTECTION, SEE DETAIL 9/C501

ROCK CONST. ENTRANCE, SEE DETAIL 6/C501 (EXACT LOCATION TO BE DETERMINED)

1150.00 TCTC - TOP OF CURB1149.50 GLGL - GUTTER LINE GO - GUTTER OUT

SPOT ABBREVIATIONS:

B - BITUMINOUS C - CONCRETE

EOF - EMERGENCY OVERFLOW G - GROUND

FFE - FINISH FLOOR ELEVATION (*) - EXISTING TO BE VERIFIED

© 2024 Larson Engineering, Inc. All rights reserved.

| CONSTRUCTION |
|-------------------------|
| DOCUMENTS |
| EVISION SCHEDULE |

| NUMBER | DESCRIPTION | DATE |
|--------|--------------|----------|
| 1 | ADDENDUM #1 | 02/12/24 |
| 2 | ADDENDUM #2 | 02/15/24 |
| 3 | ADDENDUM #3 | 02/22/24 |
| 4 | STATE REVIEW | 05/31/24 |
| 5 | PR 03 | 08/01/24 |
| 6 | PR 04 | 08/16/24 |

I hereby certify that this plan, specifications or report was prepared by me or under my direct supervision and that I am a duly licensed Professional Engineer under the laws of the state of Minnesota

Print Name: Justin Nielsen, P.E. Signature: Juto Tinh Date: 02/01/2024 Registration No. 52687

GRADING & EROSION CONTROL PLAN

C301

950 PROPOSED CONTOURS - MAJOR INTERVAL PROPOSED CONTOURS - MINOR INTERVAL GRADE SLOPE

-o-o-o-SEDIMENT LOG, SEE DETAIL 7/C501

RIP-RAP, SEE DETAIL 4/C501 AND 5/C501

INLET PROTECTION, SEE DETAIL 9/C501

 1150.00 TC
 TC - TOP OF CURB

 1149.50 GL
 GL - GUTTER LINE

ROCK CONST. ENTRANCE, SEE DETAIL 6/C501 (EXACT LOCATION TO BE DETERMINED) SPOT ABBREVIATIONS:

GO - GUTTER OUT **B - BITUMINOUS** C - CONCRETE EOF - EMERGENCY OVERFLOW

G - GROUND FFE - FINISH FLOOR ELEVATION

(*) - EXISTING TO BE VERIFIED

 \mathbf{M}

© 2024 Larson Engineering, Inc. All rights reserved.

| CONSTRUCTION | | |
|--------------------------|--|--|
| DOCUMENTS | | |
| REVISION SCHEDULE | | |

| NUMBER | DESCRIPTION | DATE |
|--------|--------------|----------|
| 1 | ADDENDUM #1 | 02/12/24 |
| 2 | ADDENDUM #2 | 02/15/24 |
| 3 | ADDENDUM #3 | 02/22/24 |
| 4 | STATE REVIEW | 05/31/24 |
| 5 | PR 03 | 08/01/24 |
| 6 | PR 04 | 08/16/24 |

I hereby certify that this plan, specifications or report was prepared by me or under my direct supervision and that I am a duly licensed Professional Engineer under the laws of the state of Minnesota.

Justin Nielsen, P.E. Junto Nichn /01/2024 Registration No. 52687

GRADING & EROSION CONTROL PLAN

C302

CABLE UNDERGROUND LINE _____ OF _____ ------ UF SANITARY SEWER PIPE WATERMAIN PIPE DRAINTILE PIPE

ELECTRIC OVERHEAD LINE ELECTRIC UNDERGROUND LINE FIBER OPTIC UNDERGROUND LINE ----- GAS ------ NATURAL GAS UNDERGROUND LINE T TELEPHONE UNDERGROUND LINE

> PIPE INSULATION, SEE DETAIL 8/C502

UTILITY NOTES

- 1. It is the responsibility of the contractor to perform or coordinate all necessary utility connections and relocations from existing utility locations to the proposed building, as well as to all onsite amenities. These connections include but are not limited to water, sanitary sewer, cable TV, telephone, gas, electric, site lighting, etc.
- 2. All service connections shall be performed in accordance with state and local standard specifications for construction. Utility connections (sanitary sewer, watermain, and storm sewer) may require a permit from the City.
- 3. The contractor shall verify the elevations at proposed connections to existing utilities prior to any demolition or excavation.
- 4. The contractor shall notify all appropriate engineering departments and utility companies 72 hours prior to construction. All necessary precautions shall be made to avoid damage to existing utilities.
- 5. Storm sewer requires testing in accordance with Minnesota plumbing code 4714.1109 where located within 10 feet of waterlines or the building.
- 6. HDPE storm sewer piping shall meet ASTM F2306 and fittings shall meet ASTM D3212 joint pressure test. Installation shall meet ASTM C2321.
- 7. All RCP pipe shown on the plans shall be MN/DOT class 3.
- 8. Maintain a minimum of 8' of cover over all water lines and sanitary sewer lines. Where 8' of cover is not provided, install 2" rigid polystyrene insulation (MN/DOT 3760) with a thermal resistance of at least 5 and a compressive strength of at least 25 psi. Insulation shall be 8' wide, centered over pipe with 6" sand cushion between pipe and insulation. Where depth is less than 5', use 4" of insulation.
- Install water lines 12" above sewers. Where the sewer is less than 12" below the water line (or above), install sewer piping of materials approved for inside building use for 10 feet on each side of the crossing.
- 10. All watermain piping shall be PVC, C900 installed with tracer wire. 11. See Project Specifications for bedding requirements.
- 12. Pressure test and disinfect all new watermains in accordance with
- state and local requirements. 13. Sanitary sewer piping shall be PVC, SDR-35, unless otherwise

noted.

14. A structure adjustment shall include removing and salvaging the existing casting assembly, removing existing concrete rings to the precast section. Install new rings and salvaged casting to proposed grades, cleaning casting flange by mechanical means to insure a sound surface and install an external chimney seal from casting to precast section. Chimney seals shall be Infi-Shield Uni-Band or an approved equal.

(C) 2024 Larson Engineering, Inc. All rights reserved.

| CONSTRUCTION | |
|------------------------|----|
| DOCUMENTS | |
| EVISION SCHEDUI | E |
| | TE |

| NUMBER | DESCRIPTION | DATE |
|--------|--------------|----------|
| 1 | ADDENDUM #1 | 02/12/24 |
| 2 | ADDENDUM #2 | 02/15/24 |
| 3 | ADDENDUM #3 | 02/22/24 |
| 4 | STATE REVIEW | 05/31/24 |
| 5 | PR 03 | 08/01/24 |
| 6 | PR 04 | 08/16/24 |
| | | |

I hereby certify that this plan, specifications or report was prepared by me or under my direct supervision and that I am a duly licensed Professional Engineer under the laws of the state of Minnesota

Justin Nielsen, P.E. Jeets Nichn /01/2024 Registration No. Date:

UTILITY PLAN

(C) 2024 Larson Engineering, Inc. All rights reserved.

| CONSTRUC | ΓΙΟΝ |
|----------------------|----------|
| DOCUMEN | TS |
| REVISION SCHE | DULE |
| JMBER DESCRIPTION | DATE |
| | 02/12/2/ |

| NUMBER | DESCRIPTION | DATE |
|--------|--------------|----------|
| 1 | ADDENDUM #1 | 02/12/24 |
| 2 | ADDENDUM #2 | 02/15/24 |
| 3 | ADDENDUM #3 | 02/22/24 |
| 4 | STATE REVIEW | 05/31/24 |
| 5 | PR 03 | 08/01/24 |
| 6 | PR 04 | 08/16/24 |
| | | |

I hereby certify that this plan, specifications or report was prepared by me or under my direct supervision and that I am a duly licensed Professional Engineer under the laws of the state of Minnesota

Print Name: Justin Nielsen, P.E. Signature: Junto Marin Date: 02/01/2024 Registration No. 52687

UTILITY PLAN

| | SYMBOL LEGEND | |
|--------|---|---|
| | CATCH BASIN | CTV CABLE UNDERGROUND LINE OE ELECTRIC OVERHEAD LINE UE ELECTRIC UNDERGROUND LINE F0 FIBER OPTIC UNDERGROUND LINE |
| 6/C502 | FLARED END SANITARY MANHOLE HYDRANT GATE VALVE & BOX | — GAS — GAS — NATURAL GAS UNDERGROUND LINE > — > — > — SANITARY SEWER PIPE > — T — T — T — TELEPHONE UNDERGROUND LINE I — I — I — I — DT — DRAINTILE PIPE |
| SEE | ⊗ WATER SHUTOFF | PIPE INSULATION, SEE DETAIL 8/C502 |

UTILITY NOTES

1. See Sheet C400 for Utility Notes.

© 2024 Larson Engineering, Inc. All rights reserved.

| CONSTRUCTION |
|-------------------------|
| DOCUMENTS |
| EVISION SCHEDULE |

| NUMBER | DESCRIPTION | DATE |
|--------|--------------|----------|
| 1 | ADDENDUM #1 | 02/12/24 |
| 2 | ADDENDUM #2 | 02/15/24 |
| 3 | ADDENDUM #3 | 02/22/24 |
| 4 | STATE REVIEW | 05/31/24 |
| 5 | PR 03 | 08/01/24 |
| 6 | PR 04 | 08/16/24 |

I hereby certify that this plan, specifications or report was prepared by me or under my direct supervision and that I am a duly licensed Professional Engineer under the laws of the state of Minnesota.

Print Name: Justin Nielsen, P.E. Signature: Junto Mahn Date: 02/01/2024 Registration No. 52687

UTILITY PLAN

© 2024 Larson Engineering, Inc. All rights reserved.

| CONSTRUCTION | | | |
|--------------|--------------|----------|--|
| DOCUMENTS | | | |
| REV | ISION SCH | EDULE | |
| NUMBER | DESCRIPTION | DATE | |
| 1 | ADDENDUM #1 | 02/12/24 | |
| 2 | ADDENDUM #2 | 02/15/24 | |
| 3 | ADDENDUM #3 | 02/22/24 | |
| 4 | STATE REVIEW | 05/31/24 | |
| 5 | PR 03 | 08/01/24 | |
| 6 | PR 04 | 08/16/24 | |

I hereby certify that this plan, specifications or report was prepared by me or under my direct supervision and that I am a duly licensed Professional Engineer under the laws of the state of Minnesota.

Justin Nielsen, P.E. Genter Nichn /01/2024 Registration No. 52687

DETAILS

© 2024 Larson Engineering, Inc. All rights reserved.

| 1 2 3 4 5 6 | ADDENDUM #1 ADDENDUM #2 ADDENDUM #3 STATE REVIEW PR 03 PR 04 | | 02/12/24 02/15/24 02/22/24 05/31/24 08/01/24 08/16/24 |
|---|--|--|--|
| | | | |
| l hereby was pre and that under th | r certify that this pla pared by me or und t I am a duly license ne laws of the state o | n, specification ler my direct s d Professional of Minnesota. | ns or report upervision Engineer |
| Print Na Signatu | ıme: Justin Niels re: J udin Tirh u | en, P.E. | |
| Date: | <u>02/01/2024</u> R | egistration No. | 52687 |
| | NUG | J J J J J J J J J J J J J J J J J J J | |
| | HAWLEY SCHO MIDDLE S | PUBL OLS Schoo | |

CONSTRUCTION

DOCUMENTS

DATE

C501

REVISION SCHEDULE

NUMBER DESCRIPTION

DETAILS

(C) 2024 Larson Engineering, Inc. All rights reserved.

| DOCUMENTS | | | |
|-----------|--------------|----------|--|
| REV | ISION SCH | EDULE | |
| NUMBER | DESCRIPTION | DATE | |
| 1 | ADDENDUM #1 | 02/12/24 | |
| 2 | ADDENDUM #2 | 02/15/24 | |
| 3 | ADDENDUM #3 | 02/22/24 | |
| 4 | STATE REVIEW | 05/31/24 | |
| 5 | PR 03 | 08/01/24 | |
| 6 | PR 04 | 08/16/24 | |
| | | | |
| | | | |

CONSTRUCTION

I hereby certify that this plan, specifications or report was prepared by me or under my direct supervision and that I am a duly licensed Professional Engineer under the laws of the state of Minnesota.

Justin Nielsen, P.E. <u>Genter Michn</u> Signature Date: 02/01/2024 Registration No. 52687

DETAILS

© 2024 Larson Engineering, Inc. All rights reserved.

| | DOCUMENTS | | | |
|--------------------------|---------------|----------|--|--|
| REVISION SCHEDULE | | | | |
| NUMBER | DESCRIPTION | DATE | | |
| 1 | ADDENDUM #1 | 02/12/24 | | |
| 2 | ADDENDUM #2 | 02/15/24 | | |
| 2 | ADDENDUM #3 | 02/22/24 | | |
| 3 | CTATE DEV/IEW | 05/31/24 | | |
| 4 | JIAIE KEVIEW | | | |
| 4 5 | PR 03 | 08/01/24 | | |

I hereby certify that this plan, specifications or report was prepared by me or under my direct supervision and that I am a duly licensed Professional Engineer under the laws of the state of Minnesota.

Print Name: Justin Nielsen, P.E. Signature: John Date: 02/01/2024 Registration No. <u>52687</u>

DETAILS

| ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ ↓ | SOD (SEE SPECIFICATIONS) TOTAL AREA: 1,042 SQUARE YARDS |
|---|--|
| + + | SEED, ALL DISTURBED AREAS (MNDOT MIX #25-131) TOTAL AREA: 5.1 ACRE |
| $\bigcirc \bigcirc \land \langle$ | ATHLETIC SEED MIX (SEE SPECIFICATIONS) TOTAL AREA: 8,455 SQUARE YARDS |
| | STORMWATER SEED MIX (MNDOT MIX #33-261) TOTAL AREA: 1,685 SQUARE YARDS |
| $\begin{array}{c} \nabla \ \nabla $ | 4" OF SHREDDED HARDWOOD MULCH OVER WEED CONTROL FABRIC. PROVIDE LANDSCAPE EDGING, AS NEEDED. TO HOLD IN THE WOOD MULCH |

LANDSCAPING NOTES

- Landscape Contractor is responsible for coordination with other contractors to protect the new improvements during landscape work activities. Report any damage to the Construction Manager immediately.
- Plant size and species substitutions must be approved in writing prior to acceptance in the field.
- 3. Landscape Contractor is responsible for ongoing maintenance of all newly installed material until time of owner acceptance. Any acts of vandalism or damage which may occur prior to owner acceptance shall be the responsibility of the contractor. Contractor shall provide the owner with a maintenance program including, but not limited to, pruning, fertilization and disease/pest control.
- 4. Landscape Contractor shall provide the owner with a watering schedule appropriate to the project site conditions and to plant material growth requirements.
- 5. Landscape Contractor shall guarantee newly planted material through one calendar year from the date of written owner acceptance. Plants that exhibit more than 10% die-back damage shall be replaced at no additional cost to the owner. The contractor shall also provide adequate tree wrap and deer/rodent protection measures for the plantings during the warranty period.
- 6. Restore all disturbed turf areas with 4" of good quality topsoil and seed/sod, as indicated.

© 2024 Larson Engineering, Inc. All rights reserved.

| REV | ISION | SCHED | ULE |
|---|---|---|--|
| NUMBER 1 2 3 4 5 6 | DESCRIPTION ADDENDUM ADDENDUM STATE REVIE PR 03 PR 04 | N #1 #2 #3 EW | DATE 02/12/24 02/15/24 02/22/24 05/31/24 08/01/24 08/16/24 |
| l hereby c was prepa and that l under the Print Nam Signature Date: <u>02</u> | ertify that this ared by me or am a duly lice laws of the st e: | s plan, specification under my direct ensed Professiona ate of Minnesota Nielsen, P.E. Registration No | ons or report supervision al Engineer |
| F | | | IC |
| M | SCH | iools SCHO | DL |

CONSTRUCTION

DOCUMENTS

LANDSCAPE PLAN

| SYI | MBOL | LEGEN | C |
|-----|------|-------|---|
| | | | |

| * * * * * * * * * * * | SOD (SEE SPECIFICAT TOTAL AREA: | IONS) 1,042 SQUARE YARDS |
|-----------------------------------|---|---|
| + + | SEED, ALL DISTURBED TOTAL AREA: | AREAS (MNDOT MIX #25-131) 5.1 ACRE |
| $\bigcirc \bigcirc \land \langle$ | ATHLETIC SEED MIX (S TOTAL AREA: | EE SPECIFICATIONS) 8,455 SQUARE YARDS |
| | STORMWATER SEED M TOTAL AREA: | IIX (MNDOT MIX #33-261) 1,685 SQUARE YARDS |
| | 4" OF SHREDDED HAR CONTROL FABRIC. PRO AS NEEDED, TO HOLD | DWOOD MULCH OVER WEED DVIDE LANDSCAPE EDGING, IN THE WOOD MULCH |

www.larsonengr.com

© 2024 Larson Engineering, Inc. All rights reserved.

| CONSTRUCTION | |
|-------------------------|--|
| DOCUMENTS | |
| EVISION SCHEDULE | |
| | |

| NUMBER | DESCRIPTION | DATE |
|--------|--------------|----------|
| 1 | ADDENDUM #1 | 02/12/24 |
| 2 | ADDENDUM #2 | 02/15/24 |
| 3 | ADDENDUM #3 | 02/22/24 |
| 4 | STATE REVIEW | 05/31/24 |
| 5 | PR 03 | 08/01/24 |
| 6 | PR 04 | 08/16/24 |
| | | |

I hereby certify that this plan, specifications or report was prepared by me or under my direct supervision and that I am a duly licensed Professional Engineer under the laws of the state of Minnesota.

Print Name: Justin Nielsen, P.E. Signature: Justin Michw Date: 02/01/2024 Registration No. 52687

LANDSCAPE PLAN

| \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ | SOD (SEE SPECIFICA TOTAL AREA: | ATIONS) 1,042 SQUARE YARDS |
|--|-----------------------------------|---|
| + + | SEED, ALL DISTURBE TOTAL AREA: | ED AREAS (MNDOT MIX #25-131) 5.1 ACRE |
| | ATHLETIC SEED MIX TOTAL AREA: | (SEE SPECIFICATIONS) 8,455 SQUARE YARDS |
| | STORMWATER SEED TOTAL AREA: | MIX (MNDOT MIX #33-261) 1,685 SQUARE YARDS |

4" OF SHREDDED HARDWOOD MULCH OVER WEED CONTROL FABRIC. PROVIDE LANDSCAPE EDGING, AS NEEDED, TO HOLD IN THE WOOD MULCH

© 2024 Larson Engineering, Inc. All rights reserved.

| HAWLEY PUBLIC SCHOOLS | • |
|--|--------------------------------|
| NUGGETCS | |
| Print Name: Justin Nielsen, P.E. Signature: Justin Maha Date: 02/01/2024 Registration No. | 52687 |
| I hereby certify that this plan, specifications o was prepared by me or under my direct supe and that I am a duly licensed Professional Eng under the laws of the state of Minnesota. | or report rvision gineer |
| 4 STATE REVIEW 05/ 5 PR 03 08/ 6 PR 04 08/ | 31/24 01/24 16/24 |
| 3 ADDENDUM #3 02/ | 22/24 |

CONSTRUCTION

DOCUMENTS

DATE 02/12/24

REVISION SCHEDULE

NUMBER DESCRIPTION 1 ADDENDUM #1

LANDSCAPE PLAN

PROJECT SPECIFIC SWPPP INFORMATION:

| I. <u>GENERAL C</u> | | | FORMATI | ON | |
|--|--|---|--|------------------------------------|---------------------------------|
| PROJECT NAME: PROJECT LOCATION: | HAWLEY PUBLIC SCHOO 1025 5TH ST. HAWLEY, MN 56549 | DLS NEW MIDDL | E SCHOOL | | |
| PROJECT CONTACTS OWNER: | HAWLEY PUBLIC SCHOO 714 JOSEPH ST, PO BO CONTACT: PHIL JENSEN | DLS (608 HAWLEY, I (218)-483-4647 | MN 56549 PJENSEN@HA\ | WLEY.K12.MN.US | |
| ENGINEER: | LARSON ENGINEERING 3524 LABORE ROAD WHITE BEAR LAKE, MN CONTACT: JUSTIN NIEL | INC. 55110 SEN, P.E., 612-23 | 31-4536, JNIELS | EN@LARSONENGR. | СОМ |
| CONTRACTOR: | COMPANY (TBD) ADDRESS CITY, STATE, ZIP CONTACT: NAME, PHON | IE, EMAIL | | | |
| CITY WHERE WORK W COUNTY WHERE WOR | ILL TAKE PLACE: K WILL TAKE PLACE: | HAWLEY, MN CLAY | | | |
| LATITUDE/LONGITUDE | OF APPROXIMATE CEN | roid of proj | ECT: 46°53'18 | .2"N 96°19'08.6"W | |
| PROJECT TYPE (CIRCL | LE ONE): RESIDENTIA | L | COMMERCIAL | /INDUSTRIAL | ROAD CONSTRUCTION |
| | RESIDENTIA | L AND ROAD CO | ONSTRUCTION | OTHER (DESCR | IBE): SCHOOL |
| DATES OF CONSTRUC Construction start da Construction comple | TION (ESTIMATED): ate: 05/2024 etion date: 05/2026 | | | | |
| PROJECT DESCRIPTIO Construction consist earthwork, stormwa | IN: ts of a new middle school, k ter basin construction, and | ous garage parkin all associated util | g lots and athletic ities and site grac | c facilities. The project ling. | includes all paving and related |
| PROJECT LIMITS: See the project plan | ns, in particular the grading | & erosion control | plans, for site dis | turbance limits. | |
| SITE DISTURBANCE SU Total number of acro Pre-Construction ac Post-Construction a Total new imperviou | UMMARY (to nearest tenth es to be disturbed: cres of impervious: cres of impervious: us acres: WATERS | acre): 13.4 Acre 0.9 Acre 6.0 Acre 5.1 Acre | | | |

| RECEIVING WATERS (WI | THIN ONE MILE OF PROJECT P | ROPERTY E | DGE): | | |
|-----------------------------|--|------------------------|----------------------------|-------------------------------|--|
| WATER BODY ID N/A N/A | NAME OF WATER BODY County Ditch 16 Buffalo River | TYPE River River | SPECIAL WATER? No No | IMPAIRED WATER? Yes Yes | |
| TOTAL MAXIMUM DA | ILY LOAD (TMDL) WATERS | | | | |

IDENTIFY WETLAND IMPACTS:

N/A

1. Will construction result in any potential adverse impacts to wetlands, including excavation, degradation of water quality, draining, filling, permanent inundation or flooding, conversion to a stormwater pond?

If yes, describe impacts and mitigation measures that were taken to address the impacts and include copies of permits or approvals from an official state wide wetland program issued specifically for this project or site:

ENVIRONMENTALLY SENSITIVE AREAS:

1. Identify adjacent public waters where the MN DNR has declared "work in water restrictions" during fish spawning timeframes: None identified.

2. Describe any stormwater mitigation measures that will be implemented, as a result of an environmental review, endangered or threatened species review or archeological site review:

PROJECT LOCATION AND RECEIVING WATERS MAP:

III. PROJECT PLANS AND SPECIFICATIONS

Refer to the project plans, specifications, geotechnical report, and stormwater calculations which depict various features that are relevant to this project. Such features may include, but are not limited to, the following:

- Project location and construction limits. • Existing and final grades, including dividing lines and direction of flow for all pre and post-construction stormwater runoff drainage areas
- located within the project limits.
- Soil types at the site.
- Locations of impervious surfaces. • Locations of areas not to be disturbed (e.g., buffer zones, wetlands, etc.)
- Sleep slope locations

Erosion Control Blanket

- Locations of areas where construction will be phased to minimize duration of exposed soils. Locations of all temporary and permanent erosion control and sediment control best management practices (BMP's).
- Buffer zones as required in item 9.17 and 23.11 of the permit.
- Locations of potential pollution-generating activities identified in Section 12 of the permit. • Standard details for erosion and sediment control BMP's to be installed at the site.

The anticipated erosion prevention and sediment control BMP quantities needed for the life of this project include the following. These quantities are estimated only and shall be verified by the Contractor.

| MP | Bidding Quantity | Final Quantity |
|---------------------------|------------------|----------------|
| ock Construction Entrance | 1 EA | |
| let Protection | 17 EA | |
| ediment Log | 3,018 LF | |
| oncrete Washout | 1 EA | |
| urf Seeding | 7.4 AC | |
| - | | |

3.457 SY

TEMPORARY SEDIMENT CONTROL (SITE SPECIFIC ITEMS)

| 1. | Is the project required to install the site is located within 1 mile No. If yes, describe (or attach plans N/A. |
|----|---|
| 2. | Will the project include dewate No. If yes, describe measures to be |
| | |

- 3. Will the project include use of filters for backwash water?

- part of a larger plan of development? Yes
- reconstructed impervious areas. installation.
- infiltration rates.

SEQUENCE OF CONSTRUCTION ACTIVITIES

- . Install stabilized rock construction entrances. Install perimeter erosion control BMP's (silt fence, bio-logs, etc). 5. Construct temporary sediment basins/traps as necessary. 6. Strip and stockpile topsoil. 7. Complete rough grading of site. 8. Stabilize denuded areas and stockpiles. 9. Install site utilities. 10. Install temporary inlet protection at newly installed catch basins/inlets. 11. Install curb and gutter and pavement sections. 12. Place topsoil and final grading of areas to be vegetated.
- control BMPs.

SEEDING NOTES AND REQUIREMENTS:

| 1. | The Contractor is responsible |
|----|-----------------------------------|
| | re-used shall be processed as |
| 2. | Prior to final seeding, all areas |

FINAL STABILIZATION:

| Ensu | re Final Stabilization of the site. |
|------|-------------------------------------|
| 1. | All soil disturbing activities at t |
| | of 80 percent of its expected fi |
| | under erosive conditions. |
| 2. | The permanent stormwater ma |
| | that are to be used as perman |
| | been removed from conveyand |

- anagement system is constructed and operating as designed. Temporary or permanent sedimentation basins nent water quality management basins have been cleaned of any accumulated sediment. All sediment has been removed from conveyance systems and ditches are stabilized with permanent cover. 3. All temporary synthetic and structural erosion prevention and sediment control BMPs (such as silt fence, bio-logs, etc.) have been removed from the site. BMPs designed to decompose on site may be left in place.
- 4. Upon correction of all erosion and sediment items and achieving vegetative cover, temporary erosion prevention and sediment control BMPs will be removed and properly disposed/recycled.
- 5. Within 30 days of final stabilization, a notice of termination shall be submitted to the MPCA (see Permit Termination Reg's).

GENERAL SWPPP NOTES:

- 2. The Contractor and all Subcontractors shall be responsible for reviewing the NPDES Permit in its entirety, to ensure that all SWPPP

SWPPP TRAINING (SECTION 21):

SWPPP PREPARER: COMPANY CONTACT

COURSE, TRAINING EXPIRATIO

SWPPP CONTACT:

CONTACT COURSE, TRAINING EXPIRATION:

CONTRAC

This SWPPP was prepared by personnel certified in design of construction SWPPP's as listed above. Copies of respective certifications are available upon request. In accordance with Section 21 of the permit, the following individuals must receive training, and the content and extent of the training is commensurate with the individual's job duties and responsibilities with regard to activities covered under the permit: a. Individuals preparing the SWPPP for the project. b. Individuals overseeing implementation of, revising and/or amending the SWPPP, and individuals performing inspections for the project.

Individuals must receive training from local, state, federal agencies, professional organizations, or other entities with expertise in erosion prevention, sediment control, permanent stormwater treatment and the MN NPDES/SDS Construction Stormwater permit. Individuals shall attend a refresher-training course every three (3) years.

INSPECTIONS AND MAINTENANCE:

https://www.pca.state.mn.us/sites/default/files/wq-strm2-36.docx **RECORDS RETENTION:**

The SWPPP, including all changes/amendments, and inspections and maintenance records shall be kept on site during normal working hours by individuals who have operational control of that portion of the site.

Section 4:

- a. The Final SWPPP b. Any other stormwater related permits required for the project;
 - c. Records of all inspection and maintenance conducted during construction;

- Sediment Control BMP's throughout the project.

a temporary sediment basin due to 10 or more acres draining to a common location, or 5 acres or more if e of a special or impaired water?

ns) showing how the basin will be designed and constructed in accordance with Section 14.

ering, basin draining?

e used to treat/dispose of turbid or sediment-laden water and method to prevent erosion or scour of discharge points (see Section 10 of the permit): N/A. Based on soil boring results, dewatering is not anticipated.

If yes, describe how filter backwash water will be managed on the site or properly disposed of:

PERMANENT STORMWATER MANAGEMENT (SITE SPECIFIC ITEMS)

1. Will the project result in one acre or more of new impervious surface or result in one acre or more of new impervious in total if the project is

If yes, a water quality volume of one inch of runoff from the cumulative new impervious surfaces must be retained on site (Section 15) through infiltration unless prohibited due to one of the reasons in item 16.14 through 16.21. If infiltration is prohibited, identify other methods of stormwater treatment used (e.g. filtration, wet sedimentation basin, regional ponding, or equivalent method): One (1) new wet pond is proposed as part of the project to provide the required water quality volume from the total new and fully

2. Attach design parameters for the planned permanent stormwater management system, including volume calculations, discharge rate calculations, construction details including basin depth, outlet configurations, location, design of pre-treatment devices, and timing for

See the project plans and stormwater calculations.

3. For infiltration systems, provide at least one soil boring, test pit, or infiltrometer test in the location of the infiltration practice for determining See the geotechnical evaluation reports contained within the stormwater calculations. Additional in-field testing and geotechnical observations are planned during construction to verify soil characteristics at the proposed basin location.

4. For projects that discharge to trout streams, including tributaries to trout streams, identify method of incorporating temperature controls into the permanent stormwater management system.

3. Install temporary construction fencing at infiltration areas and other areas not be disturbed. 4. Install inlet protection throughout project area and downstream inlets.

13. Remove accumulated sediment from basins / ponds.

14. Final grade pond and infiltration areas, including soil de-compaction as specified. 15. Complete stormwater basin as-built surveys (as required by project specifications and/or local jurisdictional authorities).

16. Complete permanent stabilization including plantings, seeding, and mulch. 17. Upon completion of construction activity and satisfactory vegetation establishment, remove remaining temporary erosion and sediment 18. Reseed / restore any areas disturbed during BMP removal.

to salvage and preserve existing topsoil as necessary for final stabilization. All topsoil to be salvaged and necessary to meet project specifications. is to be vegetated shall be scarified/decompacted and amended as specified in the plans and specifications. B. Unless otherwise noted, all seed mixes and applications shall be in accordance with MNDOT Seeding Manual, latest edition. 4. See the project plans and specifications for seed mixtures, mulch, slope stabilization, and all other landscaping requirements.

. Final Stabilization is not complete until all of the following requirements are complete: the site have been completed and soils are stabilized by a uniform perennial vegetative cover with a density inal growth over the entire pervious surface area, or other equivalent means necessary to prevent soil erosion

1. The Contractor and all Subcontractors involved with construction activity that disturbs soil, or implements a pollution control measure as part of the Storm Water Pollution Prevention Plan (SWPPP) for this project, must comply with the requirements of the National Pollution Discharge Elimination System (NPDES) / State Disposal System (SDS) Program, General Permit MNR10001, Dated August 1, 2018.

measures are in place and permit requirements fulfilled throughout the duration of the project.

| : INSTRUCTOR: ENTITY: DN: | LARSON ENGINEERING, INC. JUSTIN NIELSEN, 651.481.9120, JNIELSEN@LARSONENGR.COM DESIGN OF CONSTRUCTION SWPPP UNIVERSITY OF MINNESOTA MAY 31, 2026 |
|------------------------------------|--|
| TOR: INSTRUCTOR: ENTITY: | (TBD) NAME, PHONE, EMAIL |

c. Individuals performing or supervising the installation, maintenance and repair of BMP's.

SWPPP IMPLEMENTATION RESPONSIBILITIES:

1. The Owner and Contractor are Permittee(s) as identified by the NPDES permit.

2. The Contractor shall be responsible for all on-site implementation of the SWPPP, including all Subcontractor activities. 3. The Contractor shall provide knowledgeable and experienced person(s) in the application, installation, and maintenance of Erosion and

4. The Contractor shall provide person(s) meeting the training requirements of the NPDES permit to conduct inspection and maintenance of all erosion prevention and sediment control BMP's in accordance with permit requirements. One of these individuals must be available for an on-site inspection within 72 hours upon request by the MPCA.

5. The Contractor shall provide training documentation for all individual(s) required by the permit. This training documentation shall be recorded in the SWPPP prior to construction, or as soon as personnel for the project have been determined. Documentation shall include: a. Names of personnel associated with the project required to be trained (as listed above and under Section 21 of the permit). b. Dates of training, name of instructor, and entity providing training. c. Content of training course or workshop including number of hours of training.

1. The Contractor shall provide person(s) meeting the training requirements to conduct inspection and maintenance of all erosion prevention and sediment control BMP's under this project in accordance with permit requirements. 2. An example MPCA construction stormwater checklist can be found at the link below. Note: This template inspection report does not address all aspects of the NPDES Permit. The completion of this checklist does not guarantee that all permit requirements are in compliance; it is the responsibility of the Permittee(s) to read and understand the full permit requirements.

All Owner(s) shall keep the SWPPP, along with the following additional records, on file for three (3) years after submittal of the NOT as outlined in

d. All permanent operation and maintenance agreements that have been implemented, including all Right-Of-Way, Contracts, Covenants, and other binding requirements regarding perpetual maintenance; and e. All required calculations for design of the temporary and permanent stormwater management systems.

GENERAL SWPPP REQUIREMENTS AND NOTES

SWPPP AMENDMENTS (SECTION 6):

- 1. One of the individuals described in item 21.2.a or 21.2.b of the permit or another qualified individual must complete all SWPPP changes.
- characteristics.
- 2. The SWPPP shall be amended to include additional or modified BMPs as necessary to correct problems identified or address situations
- the discharge of pollutants to surface waters or groundwater. 3. The SWPPP shall be amended to include additional or modified BMPs as necessary to correct problems identified or address situations whenever inspections or investigations by the site owner or operator, USEPA or MPCA officials indicate the SWPPP is not effective in eliminating or significnatly minimizing the ischarge of pollutants to surface waters or groundwater or the discharges are cuasing water guality standard exceedances (e.g., nuisance conditions as defined in Minn. R. 7050.0210, subp. 2 or the SWPPP is not consistend with the ofjectives of the USEPA approved TMDL.

BMP SELECTION AND INSTALLATION (SECTION 7):

. All BMPs identified in the SWPPP document and construction plans shall be selected, installed, and maintained in an appropriate and functional manner in accordance with relevant manufacturer specifications and accepted engineering practices.

TEMPORARY EROSION PREVENTION PRACTICES (SECTION 8)

- 1. Prior to beginning any construction work at the site, locations of areas not to be disturbed must be delineated (e.g., with flags, stakes, signs, silt fence, snow fence, etc.) throughout the project site.
- 2. Minimize the need for disturbance of portions of the project with steep slopes. For those sloped areas which must be disturbed, use techniques such as phasing and stabilization practices designed for steep slopes (e.g., slope draining and terracing).
- 3. Stabilize all exposed soil areas (including stockpiles). Stabilization must be initiated immediately to limit soil erosion whenever any construction activity has permanently or temporarily ceased on any portion of the site and will not resume for a period exceeding 14 calendar days (or 7 days if within one mile of an identified impaired water). Stabilization must be completed no later than 14 calendar days (or 7 days if within one mile of an identified impaired water) after the construction activity has ceased.
- 4. Stabilization is not required on constructed base components of roads, parking lots, and similar surfaces. Stabilization is not required on temporary stockpiles without significant silt, clay or organic components (e.g., clean aggregate stockpiles, demolition concrete stockpiles, sand stockpiles) but sediment controls must be placed at the base of the stockpile.
- 5. For Public Waters that the Minnesota Department of Natural Resources has promulgated "work in water restrictions" during specified fish spawning time frames, all exposed soil areas that are within 200 feet of the water's edge, and drain to these waters must complete the stabilization activities within 24 hours during the restriction period.
- . Stabilize the normal wetted perimeter of the last 200 linear feet of temporary or permanent drainage ditches or swales that drain water from the site within 24 hours after connecting to a surface water or property edge. Stabilize remaining portions of temporary or permanent ditches or swales within 14 calendar days (or 7 days if within one mile of an identified impaired water) after connecting to a surface water or property edge and construction in that portion of the ditch temporarily or permanently ceases.
- 7. Temporary or permanent ditches or swales being used as sediment containment systems during construction (with properly designed rock-ditch checks, bio rolls, silt dikes, etc.) do not need to be stabilized during the temporary period of use as a sediment containment system. These areas must be stabilized within 24 hours after no longer being used for as a sediment containment system.
- 8. Applying mulch, hydromulch, tackifier, polyacrylamide or similar erosion prevention practices is not acceptable within any portion of the normal wetted perimeter of a temporary or permanent drainage ditch or swale section with a continuous slope of greater than 2 percent.
- 9. Pipe outlets must be provided with temporary or permanent energy dissipation within 24 hours after connection to a surface water or permanent stormwater treatment system.
- 10. Route water around unstabilized areas on the site and to reduce erosion, unless infeasible. Use erosion controls and velocity dissipation devices such as check dams, sediment traps, riprap, or grouted riprap at outlets within and along the length of any constructed stormwater conveyance channel, and at any outlet, to provide a non-erosive flow velocity, to minimize erosion of channels and their embankments, outlets, adjacent stream banks, slopes, and downstream waters during discharge conditions.
- 11. Unless infeasible due to lack of pervious or vegetated areas, direct discharges from BMPs to vegetated areas of the site (including any natural buffers) in order to increase sediment removal and maximize stormwater infiltration. Use velocity dissipation devices if necessary to prevent erosion when directing stormwater to vegetated areas.
- 12. Infiltration areas shall not be excavated until all upstream areas have been stabilized and/or upstream BMPs are in place to properly prevent sediment deposition. Only low impact equipment shall be allowed in infiltration areas which shall be clearly identified, staked, and marked/fenced off.
- 13. Project phasing shall be implemented to ensure land disturbance and temporary erosion control measures can be effectively inspected and maintained throughout the duration of the project in accordance with the Inspection and Maintenance requirements of Section 11.

TEMPORARY SEDIMENT CONTROL PRACTICES (SECTION 9)

- 1. Sediment control practices must be established on all down gradient perimeters and be located upgradient of any buffer zones. The perimeter sediment control practices must be in place before any upgradient land-disturbing activities begin. These practices shall remain in place until Final Stabilization has been established.
- 2. If downgradient sediment controls become overloaded, based on frequent failure or excessive maintenance requirements, additional upgradient sediment control practices or redundant BMPs shall be installed to eliminate the overloading concerns. All changes shall be recorded in the SWPPP.
- 3. Temporary or permanent drainage ditches and sediment basins designed as part of a sediment containment system (e.g., ditches with rock-check dams) require sediment control practices only as appropriate for site conditions.
- 4. A floating silt curtain placed in the water is not an acceptable sediment control BMP except when working on a shoreline or below the waterline. Immediately after the short term construction activity (e.g., installation of rip rap along the shoreline) in that area is complete, upland perimeter control practices shall be installed if exposed soils still drain to a surface water.
- 5. Re-install all sediment control practices that have been adjusted or removed to accommodate short-term activities such as clearing or grubbing, or passage of vehicles, immediately after the short-term activity has been completed. Complete any short-term activity that requires removal of sediment control practices as quickly as possible and re-install sediment control practices before the next precipitation event even if the short-term activity is not complete.
- 6. All storm drain inlets must be protected by appropriate BMPs during construction until all sources with potential for discharging to the inlet have been stabilized. Inlet protection may be removed for a particular inlet if a specific safety concern (street flooding/freezing) has been identified by the Permittee(s) or the jurisdictional authority (e.g., city/county/township/MnDOT engineer). The Permittee(s) must document the need for removal in the SWPPP.
- 7. Temporary soil stockpiles must have silt fence or other effective sediment controls, and cannot be placed in any natural buffers or surface waters, including stormwater conveyances such as curb and gutter systems, or conduits and ditches unless there is a bypass in place for the stormwater.
- 8. Where vehicle traffic leaves any part of the site (or onto paved roads within the site) install a vehicle tracking BMP to minimize the track out of sediment from the construction site. Examples of vehicle tracking BMPs include (but are not limited to) rock pads, mud mats, slash mulch, concrete or steel wash racks, or equivalent systems. Use street sweeping if such vehicle tracking BMPs are not adequate to prevent sediment from being tracked onto the street.
- 9. The Permittee(s) must install temporary sedimentation basins as required in accordance with permit requirements.
- 10. Minimize soil compaction by restricting vehicle access in areas where final vegetative stabilization will occur, unless otherwise infeasible.
- 11. Discharges from BMPs shall be directed to vegetated areas unless infeasible.
- surface water is located within 50 feet of the project's earth disturbances and stormwater flows to the surface water. 13. Perimeter sediment controls shall be installed at least 5 feet apart unless limited by lack of available space. Natural buffers are not required
- adjacent to road ditches, judicial ditches, county ditches, stormwater conveyance channels, storm drain inlets, and sediment basins. If preserving the buffer is infeasible, the reasons for which shall be recorded in the SWPPP.
- 14. The use of polymers, flocculants, or other sedimentation treatment chemicals, if used on the project, shall be used in accordance with accepted engineering practices, dosing specifications, and sediment removal design specifications provided by the product manufacturer or supplier. Use conventional erosion and sediment controls prior to the chemical addition to ensure effective treatment. Chemicals may only be applied where treated stormwater is directed to a sediment control system which allows or filtration of settlement of the floc prior to discharge.
- 15. If the proposed project as shown on the plans has 10 or more acres draining to a common location or 5 acres or more if the site is within one mile of a special or impaired water (as identified in Section II - Receiving Waters and Environmentally Sensitive Areas), then a temporary sediment basin must be constructed as shown on the plans. Temporary sediment basins will have a minimum of 3,600 cubic feet of storage per acre draining to the basin. The basin outlet shall provide for discharging water from the surface to minimize discharging of pollutants. A stabilized emergency overflow shall be constructed.

DEWATERING AND BASIN DRAINING (SECTION 10)

- 1. Discharge turbid or sediment-laden waters related to dewatering or basin draining (e.g., pumped discharges, trench/ditch cuts for drainage) to a temporary or permanent sediment basin on the project site unless infeasible. Discharge from the temporary or permanent sedimentation basins to surface waters if the basin water has been visually checked to ensure adequate treatment has been obtained in the basin and that nuisance conditions will not result from the discharge. If the water cannot be discharged to a sedimentation basin prior to entering the surface water, it must be treated with the appropriate BMPs, such that the discharge does not adversely affect the receiving water or downstream properties.
- 2. Discharge water that contains oil or grease, must use an oil-water separator or suitable filtration device (e.g. cartridge filters, absorbents pads) prior to discharging the water.
- 3. All water from dewatering or basin-draining activities must be discharged in a manner that does not cause nuisance conditions, erosion in receiving channels or downslope properties, erosion or scour in the immediate vicinity of discharge points, or inundation in wetlands causing significant adverse impact to the wetland.
- 4. The use of filters with backwash water, haul the backwash water away for disposal, return the backwash water to the beginning of the treatment process, or incorporate the backwash water into the site in a manner that does not cause erosion. Discharge backwash water to the sanitary sewer if permission is granted by the sanitary sewer authority. Replace and clean the filter media used in dewatering devices when required to retain adequate function.
- 5. Contractor must provide a de-watering plan to City Water resource staff prior to discharging water from de-watering operation off-site, to include: - Point(s) of discharge
- Measures used to prevent pollution from discharge (e.g. de-watering bag, sediment log, etc.) Chemicals used to settle sediment (if applicable)

Changes involving the use of less stringent BMPs must include a justification describing how the replacement BMP is effective for the site

whenever there is a change in design, construction, operation, maintenance, weather or seasonal conditions having a significant effect on

12. Preserve a 50 foot natural buffer or (if a buffer is infeasible on the site) provide redundant (double) perimeter sediment controls when a

INSPECTIONS AND MAINTENANCE (SECTION 11)

- 1. Owner and Contractor shall ensure that a trained person (as identified in item 21.2.b) of the permit will inspect the entire construction site at a minimum: - Once every seven (7) days during active construction, and
- Within 24 hours after a rainfall event greater than 1/2 inch in 24 hours
- 2. Inspect all erosion prevention and sediment control BMPs and Pollution Prevention Management Measures to ensure integrity and effectiveness during all routine and post-rainfall event inspections. All nonfunctional BMPs must be repaired, replaced, or supplemented with functional BMPs by the end of the next business day after discovery, or as soon as field conditions allow access unless another time frame is specified below. Investigate and comply with the following Inspection and Maintenance requirements:
- a. All perimeter control devices must be repaired, replaced, or supplemented when they become nonfunctional or the sediment reaches one-third (1/3) of the height of the device. These repairs must be made by the end of the next business day after discovery, or thereafter as soon as field conditions allow access. b. Temporary and permanent sedimentation basins must be drained and the sediment removed when the depth of sediment
- collected in the basin reaches one-half (1/2) the storage volume. Drainage and removal must be completed within 72 hours of discovery, or as soon as field conditions allow access. c. Surface waters, including drainage ditches and conveyance systems, must be inspected for evidence of erosion and
- sediment deposition during each inspection. Remove all deltas and sediment deposited in surface waters, including drainage ways, catch basins, and other drainage systems, and restabilize the areas where sediment removal results in exposed soil. The removal and stabilization must take place within seven (7) days of discovery unless precluded by legal, regulatory, or physical access constraints. Use all reasonable efforts to obtain access. If precluded, removal and stabilization must take place within seven (7) calendar days of obtaining access. Contact all local, regional, state and federal authorities and receiving any applicable permits, prior to conducting any work in surface waters. d. Construction site vehicle exit locations must be inspected for evidence of off-site sediment tracking onto paved surfaces.
- Tracked sediment must be removed from all paved surfaces both on and off site within 24 hours of discovery, or if applicable, within a shorter time. e. Streets and other areas adjacent to the project must be inspected for evidence of off-site accumulations of sediment. If sediment is present, it must be removed in a manner and at a frequency sufficient to minimize off-site impacts (e.g., fugitive
- sediment in streets could be washed into storm sewers by the next rain and/or pose a safety hazard to users of public streets).
- Inspection frequency adjustment: a. Inspections of areas with permanent cover can be reduced to once every 30-days, even if construction activity continues on other portions of the site; or b. where sites have permanent cover on all exposed soil and no construction activity is occurring anywhere on the site,
- inspections can be reduced to once per month and, after 12 months, may be suspended completely until construction activity resumes. The MPCA may require inspections to resume if conditions warrant; or c. where construction activity has been suspended due to frozen ground conditions, inspections may be suspended. Inspections must resume within 24 hours of runoff occurring, or upon resuming construction, whichever comes first.
- 4. All inspections and maintenance activities within 24 hours of being conducted must be recorded and retained in the SWPPP. These records must include: a. Date and time of inspections
- b. Name of person(s) conducting inspections
- c. Findings of inspections, including the specific location where corrective actions are needed d. Corrective actions taken (including dates, times, and party completing maintenance activities)
- e. Date and amount of all rainfall events greater than 1/2 inch (0.5 inches) in 24 hours. Rainfall amounts must be obtained by a properly maintained rain gauge installed onsite, a weather station that is within 1 mile of your location or a weather reporting system that provides site specific rainfall data from radar summaries.
- f. If any discharge is observed to be occurring during the inspection, a record of all points of the property from which there is a discharge must be made, and the discharge should be described (i.e., color, odor, floating, settled, or suspended solids, foam, oil sheen, and other obvious indicators of pollutants) and photographed. g. Any amendments to the SWPPP proposed as a result of the inspection must be documented within seven (7) calendar
- 5. All infiltration areas must be inspected to ensure that no sediment from ongoing construction activity is reaching the infiltration area. All infiltration areas must be inspected to ensure that equipment is not being driven across the infiltration area.

POLLUTION PREVENTION MANAGEMENT MEASURES (SECTION 12)

Implement the following pollution prevention management measures on the site:

- 1. Storage, Handling, and Disposal of Construction Products, Materials, and Wastes shall comply with the following to minimize the exposure to stormwater of any of the products, materials, or wastes. Products or wastes which are either not a source of contamination to stormwater or are designed to be exposed to stormwater are not held to this requirement
- a. Building products that have the potential to leach pollutants must be under cover (e.g., plastic sheeting or temporary roofs) to prevent the discharge of pollutants or protected by a similarly effective means designed to minimize contact with stormwater
- b. Pesticides, herbicides, insecticides, fertilizers, treatment chemicals, and landscape materials must be under cover (e.g., plastic sheeting or temporary roofs) to prevent the discharge of pollutants or protected by similarly effective means designed to minimize contact with stormwater.
- c. Hazardous materials, toxic waste, (including oil, diesel fuel, gasoline, hydraulic fluids, paint solvents, petroleum-based products, wood preservatives, additives, curing compounds, and acids) must be properly stored in sealed containers to prevent spills, leaks or other discharge. Restricted access storage areas must be provided to prevent vandalism. Storage and disposal of hazardous waste or hazardous materials must be in compliance with Minn. R. ch. 7045 including secondary containment as applicable.
- d. Solid waste must be stored, collected and disposed of properly in compliance with Minn. R. ch. 7035. e. Portable toilets must be positioned so that they are secure and will not be tipped or knocked over. Sanitary waste must be disposed of properly in accordance with Minn. R. ch. 7041.
- 2. Fueling and Maintenance of Equipment or Vehicles; Spill Prevention and Response: Take reasonable steps to prevent the discharge of spilled or leaked chemicals, including fuel, from any area where chemicals or fuel will be loaded or unloaded including the use of drip pans or absorbents unless infeasible. Conduct fueling in a contained area unless infeasible. Ensure adequate supplies are available at all times to clean up discharged materials and that an appropriate disposal method is available for recovered spilled materials. Report and clean up spills immediately as required by Minn. Stat. § 115.061, using dry clean up measures where possible.
- 3. Vehicle and equipment washing: Wash the exterior of vehicles or equipment on the project site, washing must be limited to a defined area of the site. Runoff from the washing area must be contained in a sediment basin or other similarly effective controls and waste from the washing activity must be properly disposed of. Properly use and store soaps, detergents, or solvents. No engine degreasing is allowed on site.
- 4. Concrete and other washouts waste: Provide effective containment for all liquid and solid wastes generated by washout operations (concrete, stucco, paint, form release oils, curing compounds and other construction materials) related to the construction activity. The liquid and solid washout wastes must not contact the ground, and the containment must be designed so that it does not result in runoff from the washout operations or areas. Liquid and solid wastes must be disposed of properly and in compliance with MPCA rules. A sign must be installed adjacent to each washout facility that requires site personnel to utilize the proper facilities for disposal of concrete and other washout wastes.

PERMIT TERMINATION (SECTIONS 4 AND 13)

- 1. Permittees must submit a NOT within 30 days after all termination conditions listed in Section 13 are complete
- 2. Permittees must submit a NOT within 30 days after selling or otherwise legally transferring the entire site, including permit responsibility for roads (e.g., street sweeping) and stormwater infrastructure final clean out, or transferring portions of a site to another party. The permittees' coverage under the permit terminates at midnight on the submission date of the NOT.
- 3. Permittees may terminate permit coverage prior to completion of all construction activity if they meet all of the following conditions a. Construction activity has ceased for at least 90 days; and
- b. at least 90 percent (by area) of all originally proposed construction activity has been completed and permanent cover has been established on those areas; and c. on areas where construction activity is not complete, permanent cover has been established; and

d. the site complies with items 13.3 through 13.7 of the permit. After permit coverage is terminated under this item, any subsequent development on the remaining portions of the site will require permit coverage if the subsequent development itself or as part of the remaining common plan of development or sale will result in land disturbing activity of one (1) or more acres in size.

- 4. Permittees may terminate coverage upon MPCA approval after submitting information documenting the owner canceled the project.
- 5. Permittees must complete all construction activity and must install permanent cover over all areas prior to submitting the NOT. Vegetative cover must consist of a uniform perennial vegetation with a density of 70 percent of its expected final growth. Vegetation is not required where the function of a specific area dictates no vegetation, such as impervious surfaces or the base of a sand filter.
- 6. Permittees must clean the permanent stormwater system of any accumulated sediment and must ensure the system meets all applicable requirements in Section 15 through 19 of the permit and is operating as designed.
- 7. Permittees must remove all sediment from conveyance systems prior to submitting the NOT
- 8. Permittees must remove all temporary synthetic erosion prevention and sediment control BMPs prior to submitting the NOT BMPs designed to decompose on-site may be left in place.
- 9. For residential construction only, permit coverage terminates on individual lots if the structures are finished and temporary erosion prevention and downgradient perimeter control is complete, the residence sells to the homeowner, and the permittee distributes the MPCA's "Homeowner Fact Sheet" to the homeowne
- 10.For construction projects on agricultural land (e.g., pipelines across cropland), disturbed land must be returned to its preconstruction agricultural condition prior to submitting the NOT.
- 11. When submitting the NOT, permittees must include either ground or aerial photographs showing vegetative cover requirements have been met as listed above. All submitted photographs shall include the date and specific site location.

LONG TERM OPERATION AND MAINTENANCE:

- 1. Upon the completion of construction activity and NPDES permit termination, in accordance with Sections 4 and 13, the Property Owner shall become the responsible party for long term operation and maintenance (O&M) of all permanent stormwater management features under this project.
- 2. All associated operations, inspections, maintenance, and record keeping shall be performed by trained individual(s) familiar with the site stormwater management system.
- 3. Record keeping of inspections and maintenance items shall be maintained by the Owner in accordance with applicable Maintenance Agreements/Declarations as required by local jurisdictional authorities.

(C) 2024 Larson Engineering, Inc. All rights reserved.

| CONSTRUCTION |
|-------------------------|
| DOCUMENTS |
| EVISION SCHEDULE |

| NUMBER | DESCRIPTION | DATE |
|--------|--------------|----------|
| 1 | ADDENDUM #1 | 02/12/24 |
| 2 | ADDENDUM #2 | 02/15/24 |
| 3 | ADDENDUM #3 | 02/22/24 |
| 4 | STATE REVIEW | 05/31/24 |
| 5 | PR 03 | 08/01/24 |
| 6 | PR 04 | 08/16/24 |

I hereby certify that this plan, specifications or report was prepared by me or under my direct supervision and that I am a duly licensed Professional Engineer under the laws of the state of Minnesota.

Justin Nielsen, P.E. 02/01/2024 Registration No.

SWPPP

02/01/202

